DR-OPS-012: COLD START PROCEDURES FOR AUTOMATED ASSEMBLY LINE

PDR-OPS-012: COLD START PROCEDURES

Document Classification: CONFIDENTIAL

Version: 3.2

Effective Date: January 15, 2024

Document Owner: Operations Department

Approved By: Sarah Nordstrom, COO

1. PURPOSE AND SCOPE

1. This document establishes mandatory procedures for initiating cold

2. These procedures apply to all PDR Series 7000 and 8000 autonom
2. DEFINITIONS
1. "Cold Start" refers to the initialization of AMR assembly line operation
2. "Critical Components" include BlueCore(TM) power cells, navigation
3. "Operating Temperature Range" refers to the specified temperature
3. SAFETY REQUIREMENTS
1. Personnel Requirements
Minimum two (2) certified PDR technicians must be present

2-
Valid Cold Environment Safety certification required
<u>-</u>
Appropriate cold-weather PPE must be worn at all times
2. Environmental Monitoring
-
Continuous temperature monitoring required
<u>-</u>
Humidity levels must be recorded
-
Air pressure differentials must be maintained within 5% of specified v

4. PRE-START INSPECTION PROCEDURES

- 1. Physical Inspection
- a) Verify integrity of all thermal insulation
- b) Check for ice formation on critical components
- c) Inspect seal integrity on all enclosures
- d) Confirm proper alignment of guide rails and tracks
- 2. System Diagnostics
- a) Run BlueCore(TM) diagnostic sequence
- b) Verify battery charge levels exceed 85%
- c) Confirm navigation sensor calibration
- d) Test emergency stop functionality

5. STARTUP SEQUENCE

- 1. Primary Power Initialization
- a) Engage main power distribution unit
- b) Monitor voltage stabilization for 300 seconds
- c) Verify proper phase alignment
- d) Confirm UPS backup systems are operational
- 2. Thermal Management Activation
- a) Initialize heating elements sequentially
- b) Monitor temperature gradients
- c) Verify thermal expansion compensation
- d) Confirm coolant circulation (where applicable)
- 3. Control System Boot Sequence
- a) Initialize master control unit

b) Loadgoperating parameters
c) Establish network connectivity

d) Verify redundant control systems

6. VALIDATION REQUIREMENTS

1. System Checks

- All diagnostic indicators must show green status

- Network latency must be <50ms

- Power draw within 10% of specifications

-

Temperature differentials within 2 C of setpoint

2. Documentation Requirements
-
Complete startup checklist (Form PDR-OPS-012A
-
Log all parameter readings
-
Record any anomalies or deviations
-
Obtain supervisor sign-off

7. EMERGENCY PROCEDURES

- 1. In case of system failure during cold start:
- a) Execute emergency shutdown sequence
- b) Notify facility supervisor immediately

c) Docu y nent all observatio
--

d) Initiate incident report (Form PDR-OPS-012B)

8. COMPLIANCE AND DOCUMENTATION

1. All cold start procedures must comply with:

-

OSHA Standard 1910.147

_

PDR Safety Protocol PS-2024-01

-

ISO 13849-1:2015 requirements

-

Client-specific safety requirements

2. Required Documentation
-
Completed startup checklist
-
Environmental condition log
-
System performance data
-
Technician certification records

9. REVISION HISTORY

Version | Date | Description | Approved By

2 | 2024-01-15 | Updated thermal parameters | S. Nordstrom

1 | 2023₉09-30 | Added BlueCore(TM) diagnostics | J. Barrett 0 | 2023-06-15 | Major revision | E. Frost

10. AUTHORIZATION

This document is authorized by:

...

_

Sarah Nordstrom

Chief Operating Officer

Polar Dynamics Robotics, Inc.

Date: January 15, 2024

...

11. DISCLAIMER

This document contains proprietary and confidential information below Polar Dynamics Robotics, Inc. Unauthorized reproduction or distribution strictly prohibited. PDR reserves the right to modify these procedures notice. Failure to follow these procedures may result in equipment data personal injury, and/or voiding of warranty coverage.