PDR-OPS-035 ARCTIC INSTALLATION SITE PREPARATION GUIDE

PDR-OPS-035 ARCTIC INSTALLATION SITE

Version 2.4 | Effective Date: January 15, 2024

Document Classification: Confidential - Internal Use Only

(C) 2024 Polar Dynamics Robotics, Inc.

1. PURPOSE AND SCOPE

- 1. This Site Preparation Guide ("Guide") establishes mandatory requi
- 2. This Guide applies to all PDR BlueCore(TM)-enabled autonomous

- a) Cold storage facilities
- b) Arctic industrial facilities
- c) Outdoor logistics yards in extreme cold regions
- d) Temperature-controlled pharmaceutical warehouses
- e) Frozen food processing facilities

2. DEFINITIONS

- 1. "Installation Zone" means the designated operational area where P
- 2. "Critical Infrastructure" means essential support systems including
- 3. "Thermal Envelope" refers to the controlled temperature zone when
- 4. "Site Certification" means the formal approval process conducted by

3. PRÉ-INSTALLATION REQUIREMENTS

- 1. Environmental Assessment
- a) Temperature mapping of installation zone over 72-hour period
- b) Humidity and condensation analysis
- c) Floor surface temperature gradient measurement
- d) Air flow pattern documentation
- e) Structural load capacity verification
- 2. Infrastructure Verification
- a) Dedicated 480V 3-phase power supply with N+1 redundancy
- b) Emergency power backup system rated for -50 C operation
- c) Category 6A shielded ethernet cabling with cold-rated jacket
- d) Minimum 1 Gbps network backbone

e) UPS systems with cold-start capability

4. SITE PREPARATION SPECIFICATIONS

1. Floor Surface Requirements

a) Maximum slope gradient: 1.5%

b) Minimum concrete thickness: 150mm

c) Surface flatness tolerance: FF35/FL25

d) Anti-slip coating with minimum 0.6 coefficient of friction

e) Thermal break isolation from subgrade

2. Charging Station Infrastructure

a) Minimum 2.5m x 2.5m dedicated space per station

b) 100mm raised platform with cable management system

- c) Localemergency power cutoff within 3m
- d) Temperature-monitored ventilation system
- e) Fire suppression coverage

5. SAFETY AND COMPLIANCE

- 1. Emergency Systems
- a) Emergency stop stations at 15m intervals
- b) Automated fire detection and suppression
- c) Emergency lighting rated for -50 C
- d) Backup communication system
- e) Emergency personnel refuge areas
- 2. Regulatory Compliance

- a) Locabuilding codes and permits
- b) Electrical safety certifications
- c) Fire marshal approval
- d) Insurance underwriter requirements
- e) OSHA workplace safety standards

6. VALIDATION AND CERTIFICATION

- 1. Pre-Installation Testing
- a) Power quality analysis
- b) Network latency verification
- c) Environmental control system testing
- d) Emergency system functional testing
- e) Floor load capacity validation

- 2. Site-Gertification Process
- a) Documentation review
- b) Physical inspection
- c) Systems integration testing
- d) Safety protocol verification
- e) Final approval signoff

7. LEGAL DISCLAIMERS

- 1. This Guide contains confidential and proprietary information of Pola
- 2. Compliance with this Guide does not guarantee system performance
- 3. PDR reserves the right to modify these requirements based on site

8. DOCUMENT CONTROL

Document Owner: Operations Department

Last Revision: January 15, 2024

Next Review: January 15, 2025

Document Number: PDR-OPS-035

Version: 2.4

9. APPROVAL

APPROVED BY:

_

Sarah Nordstrom

Chief Operating Officer
Polar Dynamics Robotics, Inc.
Date: _
_
Dr. James Barrett
Chief Robotics Officer
Polar Dynamics Robotics, Inc.
Date: _

