# **Installation Requirements - FrostLine Logistics Centers**

## Polar Dynamics Robotics, Inc.

Document Version: 2.4

Effective Date: January 15, 2024

#### 1. GENERAL PROVISIONS

1 This Installation Requirements document ("Requirements") sets forth the mandatory specifications and conditions for installing Polar Dynamics Robotics, Inc. ("PDR") autonomous mobile robot systems ("AMR Systems") in FrostLine Logistics Centers ("Facilities").

2 These Requirements shall be binding upon all parties involved in the installation, including PDR personnel, authorized contractors, Facility operators, and any third-party service providers.

# 2. FACILITY PREREQUISITES

#### 1 Temperature Control Systems

- Facility must maintain consistent operating temperatures between -30 C and +5 C
- Temperature variation shall not exceed 2 C within any 24-hour period
- Dedicated climate control redundancy systems must be operational
- Temperature monitoring systems must interface with PDR's IceNav platform

## 2 Floor Specifications

- Concrete slab thickness minimum 6 inches (150mm)
- Floor flatness rating: FF35 minimum
- Floor levelness rating: FL25 minimum
- Surface treatment: Non-slip, epoxy-based coating
- Maximum allowable floor gaps: 10mm
- Load capacity: Minimum 2,000 kg/m

#### 3 Network Infrastructure

- Dedicated fiber optic backbone
- Minimum 10Gb/s network capacity
- Redundant wireless access points with -85dBm minimum signal strength

- Separate VLAN for AMR operations
- UPS backup for all network components

# 3. INSTALLATION REQUIREMENTS

#### 1 Power Infrastructure

- 480V three-phase power supply
- Dedicated charging station circuits: 50A per station
- Emergency power cutoff systems at 50-meter intervals
- Ground fault protection systems
- Power quality monitoring systems

## 2 Safety Systems

- Emergency stop buttons at 25-meter intervals
- Light curtains at all interaction zones
- Safety laser scanner zones properly configured
- Audible and visual warning systems
- Fire suppression system compatibility verification

#### 3 Navigation Infrastructure

- QR code grid installation: 2-meter intervals
- Minimum lighting: 150 lux at floor level
- Reflective marker installation per PDR specification PS-2023-14
- Clear line of sight maintenance for lidar systems
- Installation of PDR IceNav beacons per zone

#### 4. ENVIRONMENTAL CONTROLS

## 1 Humidity Requirements

- Operating range: 20% to 60% RH
- Condensation prevention systems
- Dehumidification capacity: 50 liters/hour minimum
- Moisture sensors at 10-meter intervals

## 2 Air Quality

- MERV 13 filtration minimum
- Positive pressure maintenance
- Air exchange rate: 6 ACH minimum
- Particulate monitoring systems
- Anti-static controls

## 5. COMPLIANCE AND TESTING

#### 1 Pre-Installation Verification

- Site survey documentation
- Environmental compliance audit
- Power quality analysis
- Network infrastructure testing
- Floor quality assessment

#### 2 Post-Installation Testing

- Full system commissioning protocol
- Safety system verification
- Navigation accuracy testing
- Communication system validation
- Performance benchmark testing

## 6. MAINTENANCE ACCESS

# 1 Service Areas

- Minimum 2-meter clearance around charging stations
- Dedicated maintenance bays: 1 per 10 AMR units
- Tool storage and workspace requirements
- Spare parts storage area: 20m minimum
- Technical documentation station

## 7. LEGAL COMPLIANCE

1 The installation must comply with:

- OSHA workplace safety requirements
- ANSI/RIA R15.06 safety standards
- Local building codes and regulations
- Fire safety regulations
- Insurance underwriter requirements

# 8. WARRANTY AND LIABILITY

1 Failure to maintain these Installation Requirements may void PDR's equipment warranty and performance guarantees.

2 PDR assumes no liability for system failures or performance issues resulting from non-compliance with these Requirements.

#### 9. MODIFICATIONS

1 These Requirements may be modified only in writing by authorized PDR representatives.

2 Facility operators must obtain written approval from PDR before implementing any modifications that may affect AMR System operation.

## **EXECUTION**

IN WITNESS WHEREOF, the undersigned acknowledges receipt and understanding of these Installation Requirements.

Facility Operator: _		
Name: _		
Title:		
Date:		
PDR Representative:		
Name: _		
Title:		
Date:		

End of Document